

ADDENDUM 1

DATE: 6-21-2024

GENERAL

Question: What is the estimated Start + Completion date?

Answer: 8/1/2024 - 10/30/2024

Question: Are permit fees waived?

Answer: The City Permit fees are waived BUT not the State Education Fund Fee or any other State Fees that may be associated.

Question: Do you required our DAS Prequalification certificate to be submitted with our proposal?

Answer: Yes

Question: Is this project CHRO?

Answer: Yes

Question: Is maintenance required on the units once installed? If so, for how long? This would be separate from the workmanship warranty.

Answer: No, not at this time.

Question: Please confirm that MC will be acceptable to run for the indoor branch circuits.

Answer: MC cable may be used as specified. Please refer to Specifications Section 26 05 00, paragraph 3.4G.

Question: Please confirm THHN is acceptable for the feeder / branch wiring.

Answer: It is not acceptable to use THHN for feeder/branch wiring. Please refer to specifications section 26 05 00, paragraph 2.7.

Question: Please confirm EMT with raintight fittings are acceptable for exterior use.

Answer: EMT with raintight fittings are not acceptable for exterior use. Please refer to Specifications section 26 05 00, paragraph 2.3.A.

Question: Will PVC be acceptable for the condensate drain piping?

Answer: PVC is not acceptable for condensate drain piping.

Question: Please confirm if the condensate piping will need to be insulated and what thickness of insulation?

Answer: Condensate piping shall be insulated. Please refer to Specification section 23 07 00, paragraph 2.1

Question: Will 2" insulation be required for the exterior piping?

Answer: Please refer to Specifications section 23 07 00, paragraphs 2.1 and 2.2.

Question: Will the contractor need to provide a fence around all of the new condensers, or will the town provide them after the project is complete?

Answer: Yes, Contractor to provide Fencing.